

GAVIN RHODES

—Landscapes Ltd—

56A Leeds Road, Mirfield, West Yorkshire WF14 0DE
T: 01924 491 439 E: info@gavinrhodes.co.uk W: www.gavinrhodes.co.uk

Mr Richard Butterfield
Wolfstones Heights Farm
Wolfstones Road
Upperthong
Holmfirth
HD9 3UU

QUOTATION

Quotation to supply/carry out all works to change verges (highlighted in red on plan) to incorporate a permeable grid system walkway finished with a grassed surface.

Schedule of proposed spec for the works –

1. The schedule works for the Verge Works shall consist of the following:
 - 1.1 Turf strip removal of existing Verges across entire length and width (but no greater than this)
 - 1.2 The removal of the undersoil and stone to a 200mm depth whichever across the entire existing length and width of the Verges (but no greater than this) with no intervention on the existing Highway surface including the accessway to Wolfstone Heights on the Land which bisects the Verges
 - 1.3 Compacted stone sub-base material that is permeable and suitable for a the 'Cellpave 40' cellular lattice paving grid as identified or similar to that supplied at:
<https://www.groundtrax.com/cellpave-40-porous-plastic-pavers/> backfilled to 150mm depth
 - 1.4 Application of membrane and topsoil bedding layer to across entire length of Verges on top of sub-base material to 50mm depth.
 - 1.5 Heavy grass-seeding application of topsoil bedding layer.
 - 1.6 Application of the cellular lattice paving grid compacted into the seeded topsoil bedding layer to meet flush with the existing Highway surface not forming part of the Verges.

This quote excludes any necessary agreements or consents required from the council as we believe that the verge is adopted highway.

Total £6135.00 + vat

DESIGN • CONSTRUCTION • MAINTENANCE